

The heavy gas system

Sosuke Horikawa, University of Zurich with Jacky Rochet, Olav Ullaland and Vitali Polyakov

16 November 2006, DIRAC Meeting at CERN

Radiator gas - C_4F_{10}



Radiator gas recirculation system

- To fill up the detector with C_4F_{10} without a significant loss of the gas
 - Recirculation cycle, with separation of the Ar/N₂ and C₄F₁₀ \rightarrow
 - To maintain the purity of the radiator gas
 - Recirculation through the water absorber and the separation unit
- To collect the gas back to the reservoir after the run (or whenever needed)
- To automatically regulate the pressure inside the detector vessel in ±5 mbar range

Radiator gas recirculation system

Separation unit



- Gas-liquid separator tank in the fridge (-18 °C, ~2 bar)
- Separate Ar/N₂ and C₄F₁₀ by means of clearly different boiling points
- Membrane module
 - Selectively vent Ar/N₂ to the air by means of smaller kinetic diameter of the molecules
- Water absorber
 - Molecular sieve (4 A)
- Ar/N₂ supply

Full scheme



Main recirculation line



Membrane filter



Flow Ar/N₂



Under construction

August 2006









Where is the rack?





The Rack

Freezer





Piping

Back





Wiring



In the Freezer

Heat exchanger coil

Glass tube

Gas/liquid separator tank / Reservoir ~30 liter



Near-detector panel





$N_2\ circulation\ test$ in the rack

- Output and input short-circuited
- Done in September and October
- Leak test : Major leaks fixed
 - Leak rate < 0.1 liter/h = 6 CHF/day</p>
- Manual control :Works well
- Automatic pressure regulation :
 - 9
- Two pressure switches tested and working well

Plans (I)

- Final connection between the near-detector panel and the detector
 - this evening after 17h
- Leak test of the whole system? Detector vessel??
- \bigcirc Test of the pressure sensor for the detector with N₂
- Recirculation test with N_2 for the full system
 - by the end of the year

Plans (2)



- ➡ When?
- Estimation :
 - 2-3 days for the regeneration of the molecular sieves
 - I week for cleaning the system with N_2
 - 2-3 days for the filling

Conclusions

- Construction mostly done
- Test of the full system by the end of the year
- Can be ready for the run in one month