



UPPSALA
UNIVERSITET



Uppsala Commitment to ESS and FREIA Planning

Roger Ruber
for the FREIA team
Dept. of Physics and Astronomy
Uppsala University

Concentrating on RF and instrumentation ...


- Cyclotron (since 1948)
- CELSIUS ring (1984 – 2006)
- CTF3 / CLIC
 - Two-beam Test Stand & RF breakdown issues
 - FP6-EuroTeV, FP7-EuCARD
 - NorduCLIC
- FEL
 - FLASH Optical Replica Synthesizer,
 - XFEL Laser Heater
 - Stockholm-Uppsala FEL Centrum
- ESS
 - RF systems




- Lund, Sweden, next to MAX-IV
 - 17 member states
- 5 MW pulsed neutron source
 - 14 Hz rep. rate, 4% duty factor
 - >95% reliability for user time
- Cost estimates (2008 prices)
 - 1,5 G€/ 10 years
 - 50% by Sweden, Denmark, Norway
- Time frame:
 - 2019 first neutrons
 - 2019 – 2025 consolidation and operation
 - 2025 – 2040 operation
- High intensity allows studies of
 - complex materials, weak signals, time dependent phenomena




ESS Time Line for Construction





- single pass linear proton accelerator
 - 5 MW p⁺: 50 mA, 2.5 GeV, 14 Hz, 2.86 ms
 - < 1 W/m losses
 - 95% user beam time reliability
- ~200 RF systems (352 + 704 MHz)
 - NC or SC accelerating cavity
 - RF source, amplifiers, distribution, controls
- auxillary systems
 - cryogenics, water and air cooling





Why RF Development and Testing?



- **Validation technical design and performance**
 - validation under close-to-realistic conditions
 - ensure reliability & contingency
 - ease of installation & maintenance
- **Optimization technical design**
 - improve cost, energy and resource effectiveness for construction & operation
- **Acceptance testing of series components**
 - RF system: power source, amplifiers, distribution and controls
 - complete cryomodules with multiple cavities & components
- **Training of staff**
 - participate in testing to prepare for operation



- **2009**

- ESS has need for R&D and test stand,
 - but small staff, no buildings, existing test stands occupied
- start discussion with UU on 704 MHz RF development
- proposal for ESS dedicated test facility at UU

- **2011**

- Spring:
 - ESS-UU contract on 704 MHz RF R&D
 - ESS changes to 14 Hz rep rate, 2.89 ms beam pulse
- Fall:
 - ESS changes pulse modulator strategy ' delays UU test stand

- **2012**

- UU starts work on 352 MHz RF for spoke resonators
 - spoke resonators require new power source development
 - spoke resonators have never been used in an accelerator
- maintain compatibility with 704 MHz development

1) Contribution to the Technical Design Report (WP8)

- design concept 352 MHz spoke source
- design concept RF distribution

2) Contribution to the construction planning effort (WP19)

- survey test stand infrastructure and requirements
- study of upgrade scenarios RF systems for ESS power upgrade

3) Development 352 MHz RF power amplifier for spokes (WP19)

- 1st prototype, soak test with water load and SRF spoke resonator, incl. LLRF

4) RF system test prototype spoke cryomodule (WP19)

- high power test with 2nd RF power amplifier and LLRF

5) Acceptance testing spoke cryomodules (under discussion)

- for all final cryomodules before installation

6) Development klystron pulse modulator (under discussion)

- full soak test incl. klystron and RF system, if available with SRF cavity



Where do we fit in ...



ESS Test Stand Matrix		f	P	Pupg	cryo	prototype		high power		series		high power	
		[MHz]	[kW]	[kW]		low power	when	where	when	low power	when	where	when
P0	Structures												
	ion source	--	--	--	--	LNS		LNS					on site
	LEBT buncher	352	10		--	LNS ?		LNS ?					on site
	RFQ	352	1000		--	CEA		CEA					on site
	MEBT	--	--	--	--	ESS-B ?		ESS-B ?					on site
	DTL	352	2100		--	LNL		CERN					on site
	spoke resonators	352	400	800	y	IPNO		UU					UU ?
	medium beta elliptical	704	500	1000	y	CEA ?		CEA ?		DESY ?			DESY ?
	high beta elliptical	704	900	1800	y	CEA		CEA ?		DESY ?			DESY ?
P1	Couplers												
	spoke resonators	352	800	1600	--	IPNO		CEA		??			??
	medium beta elliptical	704	650	1300	--	CEA ?		CEA ?		??			??
	high beta elliptical	704	1200	2500	--	CEA		CEA ?		??			??
P2	RF System												
	modulator		1x 3 MW klystron	5600	--	--	--	IPNS ?		--			
	modulator		2x 1.5 MW klystron	5600	--	--	--	UU ?		--			
	NC linac		1 mod. + 1 kl. + RFQ/DTL	2800	--	--	--	UU		--			
	spoke		1 source (tbd) + 1 spoke	400	--	--	--	UU		--			
	elliptical		1 mod. + 2 kl. + 2 cavities	1300	--	--	--	UU ?		--			
P3	Cryomodule												
	spoke		2 cavities	2x P2	y	IPNO		IPNO/UU					UU ?
	SPL prototype		4 cavities	1x 1500	y	CERN		CERN		--			
	ESS prototype		4 cavities	???	y	CEA ?				--			--
	low beta elliptical		6 cavities	6xP2 or 1x5000	y	--	--	--	--	DESY ?			DESY ?
	high beta elliptical		8 cavities	8xP2 or 2x5000	y	--	--	--	--	DESY ?			DESY ?




Facility for Research Instrumentation and Accelerator Development

- Cryogenic centre (kryocentrum):
 - liquid helium and liquid nitrogen production and distribution
 - horizontal test cryostat
- RF test stands (ESS RF development)
 - 352 MHz RF source prototyping for ESS spoke cavities
 - spoke cryomodule prototyping and acceptance testing at full power
- General infrastructure
 - small workshop with “clean” room (preparation vacuum chambers)
 - control room for operation cryo plants, RF systems and experiments
 - concrete bunkers for RF and neutron experiment stations

		2011				2012				2013				2014				2015			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
FREIA																					
Experiment hall	construction																				
Cryogenics	design, tender & fabrication																				
	operation																				
352 MHz Test Stand	design, tender & fabrication																				
	operation																				
Cryomodule Stand	design, tender & fabrication																				
	operation																				

How?

1. space
 - new 1000 m² FREIA hall
2. electricity, air conditioning, water cooling
3. cryogenic cooling (LHe)
 - new 100 l/h liquefier
4. radiation protection shielding (neutrons, X-rays)
5. specific test equipment
 - cryostat
 - RF power
6. people
 - accelerator group
 - TSL
 - FREIA



Construction Progress





Dependencies and Deliverables



		2011				2012				2013				2014				2015			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Dependencies by ESS AB to UU																					
Spoke resonators	prototype cavity												31/12								
	prototype cryomodule																31/12				
LLRF system	prototype for single load/cavity									30/06											31/12
	prototype for cryomodule																31/12				

Deliveries by UU to ESS AB		2011				2012				2013				2014				2015			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
WU 8.6	report, spoke source								15/10												
WU 8.9	report, RF distribution								15/10												
WU 19.3	report, test stand survey												31/12								
WU 19.4	report, RF system upgrade													30/06							
WU 19.5	report, spoke source proto																31/12				
WU 19.6	report, spoke cryomodule																				31/12



FREIA Planning



		2011				2012				2013				2014				2015			
		Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
FREIA																					
Experiment hall	construction												01/07								
Cryogenics	design, tender & fabrication												31/12								
	operation																				
352 MHz Test Stand	design, tender & fabrication												31/12								
	operation																				
Cryomodule Stand	design, tender & fabrication																31/12				
	operation																				
Project 1: Contribution to Technical Design Report																					
WP 8	RF Systems																				
WU 8.6	352 MHz power source																				
WU 8.9	RF distribution																				
Project 2: Contribution to Construction Planning Effort																					
WP 19	Test Stands																				
WU 19.1	Management																				
WU 19.3	Test stand survey																				
WU 19.4	RF systems for power upgrade																				
Project 3: Development of a Prototype RF System for Spoke Resonators																					
WU 19.5																					
Power source (proto)	identify requirements																				
	design & tender																				
	fabrication																				
RF distribution	identify requirements																				
	design & tender																				
	fabrication																				
LLRF prototype	arrival at UU from ESS AB											01/04									
Test with water load	installation & test																				
Spoke prototype	arrival at UU from ESS AB																				
	installation & test																				
	test report to ESS AB																			31/12	
Project 4: High Power Test of a Prototype Spoke Cryomodule																					
WU 19.6																					
Power source (2nd)	design & tender																				
	fabrication																				
RF distribution	design & tender																				
	fabrication																				
Cryomodule prototype	arrival at UU from ESS AB																				
	installation & test																			01/10	
	test report to ESS AB																				31/12