

Thermal compensation of SPS optical delay lines

Reference signal distribution within the LLRF lab complex



SPS damper pickup and test point signal fan-out

A. Lassak

25. August 2016


Motivation

- SPS reference RF signals are generated in BA3
- SPS damper installed in BA2 (opposite direction than the beam is circulating)
- RF signals have to be made synchronous in BA2




How is the delay achieved

- Delays of several tens of μs can be easily obtained using single mode optical fibres with analogue optical transceivers



Status after summer 2015

- Thermal drift of optical fibre measured and characterized
- Prototype regulator designed and performance tested
- PCB design and mechanical parts drawings finalized, ready for production




Maximum fibre temperature variation as a function of total fibre delay and tolerated delay drift.

Tolerated delay drift for correct damper operation is typically ± 125 ps.


Design of thermally insulated enclosure

- Set-point temperature set above ambient, no need for active cooling
- Evenly spaced 8x heating MOSFET and 8x PT1000 temperature sensor
- Total available heating power of ~ 70 W




Design of regulator

- Fully analogue circuit
- PI topology
- Designed such that temperature induced drifts within the regulator are cancelling-out → very robust topology




Fully assembled chassis (July 2016)



State of the regulator...

'Sweet spot' – set-point temperature reached



'Hotter' than set-point temperature. Should never reach this state under normal operation.

'Colder' than set-point temperature. Deviation during the initial warm-up.

Detail of optical fiber

- Fiber is split in two, for precise trimming of total electrical length


Configuration of fibers:

$$7.2 \mu\text{s} = 6.7 \mu\text{s} + 0.5 \mu\text{s}$$

$$8.15 \mu\text{s} = 7.65 \mu\text{s} + 0.5 \mu\text{s}$$

$$9.8 \mu\text{s} = 9.3 \mu\text{s} + 0.5 \mu\text{s}$$

$$10.4 \mu\text{s} = 9.9 \mu\text{s} + 0.5 \mu\text{s}$$




PT1000

Heating block

Heating MOSFET


Regulator performance test

- Entire chassis was put into thermal chamber, 20°C step in ambient temp.



Electrical delay stability

- Group delay of the longest (10.4 μ s) fiber
- Only 200 ps drift over 20 °C step in ambient temperature
- Both traces were captured after several hours




Installation in BA2

BA3


Foreseen configuration of cascaded delay lines

Fibers were configured to total length for each signal, therefore they are fed individually from this point

BA2




Chassis installed in BA2



Performance under real conditions

- Chassis was installed in BA2 on 10. August 2016
- Measured ambient temperature in BA2 varying between 22°C and 29°C
- First tests with ion beam revealed that the achieved total fiber delay for the two pick-ups is well within tolerable limits
- Fiber temperature level was found to be constant at 45°C since instalment




Other projects I was working on during my stay

- Reference Signal Distribution in LLRF Labs
- SPS Damper Pickup and Test Point Signal Fan-out

Reference Signal Distribution in LLRF Labs

- A spare HIE-Isolde GPS reference is running in the lab
- A 2nd hand rubidium oscillator is running in the lab
- 864-R-C08 is a fiber starpoint with connections to all LLRF labs
- ...10MHz reference anyone?




Sockets for labs distribution

Optical outputs for between labs distribution

SMA outputs for local distribution

Reference Signal Distribution in LLRF Labs


- Two designs; Fiber to SMA distributor and SMA to Fiber distributor
- BW ~ 5 MHz to 1 GHz
- Single rail power supply 6 V, ~0.5 A per board
- Based on Finisar FTLF1321 transceiver modules



SMA distributor board

- 1x Fiber/SMA input to 8x SMA output


0 Ω resistor to select between inputs



Frequency response of Fiber to SMA distributor


Gain vs. Frequency -3 dB @ 1 GHz

*SMA input was used for this measurement




Fiber distributor board

- 1x SMA input to 4x Fiber output



Frequency response of SMA to Fiber distributor


Gain vs. Frequency -3 dB @ 850 MHz



*Both distributors were linked together for this measurement

Phase noise measurement

- HIE-ISOLDE GPS Reference as source of 10 MHz




Output from both distributors linked together

Output from GPS reference

Phase noise measurement

- Signal generator SMC100A as source of 10 MHz




Output from both distributors linked together

Output from signal generator

Phase noise measurement

- Signal generator SMC100A as source of 200 MHz




Output from both distributors linked together

Output from signal generator

Phase noise measurement

- Signal generator SMC100A as source of 400 MHz




Output from both distributors linked together

Output from signal generator



SPS Damper Pickup and Test Point Signal Fan-out

- BW < 250 MHz
- 50 Ω input/output characteristic impedance
- Signal level max. 10 dBm
- Gain 0 dB
- Full BW on through output for switching matrix




Frequency response of test circuit

Gain vs. Frequency -3 dB @ 800 MHz; input power 10 dBm



SPS Damper Pickup and Test Point Signal Fan-out

- Prototype PCB sent for production



Questions?



www.cern.ch

Thank you for your attention

